

Hangzhou Easy Electric Wire and Cable Co., LTD

Add: Room 305, Building 2, No. 380 Fengxin Road, Hangzhou, China

www.eescable.com

Test Report

Products	ABC Palomino		Size	3*2+2AWG			
Standard	ICEA S-76-474	Invoice No.	20230803005	Date	2023.08.03		
NO.	ltem	Standards and Requirements		Test Results	Evaluation		
	Structure						
1	Phase Core						
1-1	Number of core	3		3	Qualified		
1-2	Conductor Structure	7*2.47mm		7*2.47	Qualified		
1-3	Conductor Material	AL		AL	Qualified		
1-4	Outer Stranding Direction Of Lay	Rightward		Rightward	Qualified		
1-5	Lay Ratio	10-14		13.2	Qualified		
1-6	Conductor Dia.	7.41mm		7.41	Qualified		
2	Insulation						
2-1	Insulation Material	Weatherability-XLPE		Weatherability- XLPE	Qualified		
2-2	Color	E	Black	Black	Qualified		
2-3	Average Thickness Of Insulation	≥1	.14mm	1.20 1.21 1.22	Qualified		
2-4	Min. Thickness Of Insulation	≥1	.0mm	1.09 1.10 1.12	Qualified		
2-5	Surface Of Insulation	Smoo	oth, Clean	Smooth, Clean	Qualified		
2-6	Printing Of Insulation	manufactur size, voltag should be	nould contains er, product and ge etc. Printing e clear, easily red, fastness	Passed	Qualified		
3	ACSR Neutral line						
3-1	Steel Wire	1*2	2.67mm	1*2.68	Qualified		



Hangzhou Easy Electric Wire and Cable Co., LTD

Add: Room 305, Building 2, No. 380 Fengxin Road, Hangzhou, China

www.eescable.com

				122			
3-2	AL. Wire	6*2.67mm	6*2.67	Qualified			
3-3	Outer Stranding Direction Of Lay	Rightward	Rightward	Qualified			
3-4	Lay Ratio	10-14	13.3	Qualified			
3-5	Conductor Dia.	8.01mm	8.02	Qualified			
3-6	Overall breaking force	12.7KN	13.2	Qualified			
4	Electrical Performance						
4-1	20℃ Max D.C Resistance Of Phase Conductor	≤ 0.8577 Ω/KM	0.8532	Qualified			
4-2	20°C Max D.C Resistance Of Messenger Conductor	$\leqslant~$ 0.8535 Ω /KM	0.8455	Qualified			
4-3	Alternating Voltage Stress Testing (3.5kv/1min)	No Breakdown	No Breakdown	Qualified			
5	Insulation Machinery Performance						
5-1	Elongation At Stress	≤175%	50%	Qualified			
5-2	Permanent Elongation After Cooling	≤15%	0%	Qualified			

Tested by: Shaoqiong He

Checked by: Guohui Xu